

Moorebank Precinct West Intermodal Terminal Facility - Modification

Stormwater Assessment



SIMTA

SYDNEY INTERMODAL TERMINAL ALLIANCE

Part 4, Division 4.1, State Significant Development

CONTACT



DAVID STONE Stormwater and Utilities Team Leader

T 02 8907 8294 M 0428 444 245 E david.stone@arcadis.com Arcadis Level 5, 141 Walker Street North Sydney NSW 2060

MOOREBANK PRECINCT WEST CONCEPT PLAN AND EARLY WORKS **MODIFICATION**

Stormwater Assessment

Author David Stone

per. Rd he Checker **Brad Lusty**

Approver Westley Owers

Report No MCPN-ARC-CV-RPT-0001

8/06/2016 **Date**

Revision Text

This report has been prepared for Qube in accordance with the terms and conditions of appointment for MPW Concept Plan and Early Works Modification. Arcadis Australia Pacific Pty Limited (ABN 76 104 485 289) cannot accept any responsibility for any use of or reliance on the contents of this report by any third party.

REVISIONS

Revision	Date	Description	Prepared by	Approved by
1	9/5/2016	Draft for Internal Review	DS	SB
2	24/05/2016	Draft for Client Review	DS	SB
3	8/06/2016	Final	DS	WO

CONTENTS

1 INTRODUCTION	1
1.1 Proposed works	1
1.2 Assessment purpose	3
2 MOOREBANK PRECINCT WEST CONCEPT PLAN APPROVAL	4
3 BULK EARTHWORKS DESIGN	4
4 IMPACT ASSESSMENT	4
4.1 Additional development impacts	4
5 MITIGATION MEASURES	5
6 CONCLUSION	7

1 INTRODUCTION

The Moorebank Intermodal Company (MIC) has received Concept Plan Approval, under Part 4, Division 4.1 of the *Environmental Planning and Assessment Act* 1979 (EP&A Act), to develop the Moorebank Precinct West Terminal Project (MPW Project) on the western side of Moorebank Avenue, Moorebank, in south-western Sydney (the MPW site).

On 4 June 2015, the MIC, with the approval of the Commonwealth Government, entered an agreement with the Sydney Intermodal Terminal Alliance (SIMTA) under which SIMTA will obtain approvals, build and operate all stages of the MPW Project at Moorebank. SIMTA is seeking approval to modify the MPW Concept Proposal and Stage 1 (Early Works) approval (SSD_5066) (MPW Concept Plan Approval).

The Environmental Impact Assessment (EIS) prepared for the Concept Plan Approval identified that fill material required for the development of the MPW site would be largely sourced from excavations within the MPW site and hence imported fill volumes for the project would be relatively minor. Subsequent civil design development for the MPW Project has identified that fill required to be imported to the MPW site is estimated at 1,600,000 cubic metres (m³). It is proposed to undertake additional site preparatory works, including the import, placement and stockpiling of clean fill, as a modification to the approved Stage 1 (Early Works).

This Stormwater Assessment Report has been prepared to support an application made under section (s) 96(2) of the EP&A Act to modify the MPW Concept Plan Approval (SSD_5066).

1.1 Proposed works

It is proposed to undertake additional site preparatory works, including the import, placement and stockpiling of clean fill, as a modification to the approved Early Works. The proposed modification would result in an intensification of activity associated with the approved Early Works. The works, for which a modification is sought (the Modification Proposal), include the following:

- Minor vegetation removal (not Endangered Ecological Communities, slightly above that provided within Early Works)
- Import, by truck, of approximately 1,600,000m³ of fill (from offsite locations)
- Stripping and stockpiling of topsoil within the area of impact, cut and fill (within the primary earthworks areas) and stockpiling of clean fill within the primary earthworks areas (see Figure 1)
- Temporary sediment and erosion control works, including onsite detention basins (greater than those envisaged within the Early Works)
- Establishment of temporary internal haulage routes, construction compounds (including, but not limited to, a materials crusher and other plant and equipment) (additional to those included within Early Works).

Figure 1 shows the location and extent of the Modification Proposal, which would occur largely within the footprint of the approved Early Works.

It is anticipated that the Modification Proposal works would be undertaken during the hours identified in Table 1. These hours extend those identified in the MPW Concept Plan documentation to include the evening period between 6pm-10pm on weekdays and Saturday afternoons between 1pm and 6pm.




Figure 1 Proposed earthworks (MPW Concept Plan Modification)

Table 1 Proposed working hours

Day	Proposed Hours	Activities
	6:00am – 7:00am	Material Delivery.
		Material Delivery
	7:00am – 6:00pm	Direct Placement; and
Weekdays	7.00am – 0.00pm	Stockpiling; and
vvoondayo		Crushing.
		 Material Delivery; and
	6:00pm – 10:00pm	Direct Placement; or
		Stockpiling.
	7:00am – 8:00am	 Material Delivery; and
		Direct Placement; or
		Stockpiling.
		Material Delivery
Saturdays	8:00am – 1:00pm	Direct Placement; and
Oaturdays	0.00am = 1.00pm	Stockpiling; and
		Crushing.
		 Material Delivery; and
	1:00PM - 6:00PM	Direct Placement; or
		Stockpiling.

1.2 Assessment purpose

This Stormwater Assessment Report has been prepared to provide further information on, and environmental assessment of, the Modification Proposal. The Modification Proposal has been reviewed against the Secretary's Environmental Assessment Requirements (SEARs, SSD 5066) and documentation prepared for the MPW Concept Plan Approval and applicable legislation and guidelines to determine whether the works and associated impacts of the Modification Proposal are 'substantially the same development' as that proposed under the MPW Concept Plan Approval.

2 MPW CONCEPT PLAN APPROVAL

The Surface Water Assessment prepared for the MPW Concept Plan EIS addressed water quality and potential impacts across the entire MPW site, however only the Early Works component of the proposal is approved under the MPW Concept Plan.

The Surface Water Assessment prepared to support the MPW Concept Plan EIS (PB 2014) considered the potential surface water impacts associated with the establishment of construction facilities and demolition or relocation of existing buildings and structures. The mitigation measures included the development of a soil and water management plan and erosion and sediment control plans.

3 BULK EARTHWORKS DESIGN

A preliminary bulk earthworks design for the imported fill placement area has been prepared as part of this Modification Proposal. This work includes placement of fill in accordance with geotechnical requirements then stockpiling on top of "placed" material. **Appendix A** contains a drawing package including:

- Erosion and sediment control plan
- Erosion and sediment control details
- Earthworks plan (including typical sections)

The preliminary erosion and sediment control plan has been developed in accordance with 'Managing Urban Stormwater: Soils and Construction', 4th edition (Landcom, 2004). The plan proposes swales/earth banks to collect all runoff generated from the top of the proposed stockpile. A number of chutes are then proposed to convey concentrated flows down the batters. All runoff collected from the stockpile and the immediate surrounds will be directed to sediment basins prior to discharge via existing stormwater systems. Where practical, clean water diversions will be used to divert flows generated from outside the works footprint to prevent them from entering the sediment basins.

The preliminary bulk earthworks design has been prepared with consideration of geotechnical advice included in **Appendix B**.

4 IMPACT ASSESSMENT

4.1 Additional development impacts

The additional impacts associated with the Modification Proposal relate largely to the stockpiling of imported fill. The stockpiling represents an intensification of the potential erosion and sedimentation impacts identified in the approved Early Works which included:

- increased turbidity of waterways and drainage lines
- increased nutrient loads to receiving waterways
- · changes to groundwater levels and systems
- changed concentration of stormwater pollutants
- changes to volume and velocities of surface water drainage
- sedimentation of creeks and drainage lines

The preliminary erosion and sediment control plan and details that have been prepared (refer Appendix A) provide the principles which will be used to manage these potential impacts.

5 MITIGATION MEASURES

Mitigation measures identified within the SRtS and the MCoA for the MPW Concept Plan Approval that are applicable to the management of stormwater impacts and would be implemented during the Modification Proposal are listed in Table 2.

Table 2 Mitigation measures within the REMMs and MCoAs applicable to stormwater management for the Modification Proposal

REMM / MCoA No.	Mitigation measure
9A	A soil and water management plan (or equivalent) would be developed before work begins in the conservation area. This plan would include erosion and sediment control plans (ESCPs) and procedures to manage and minimise potential environmental impacts associated with developing this area.
9B	Site compounds, stockpiling areas and storage areas for sensitive plant, equipment and hazardous materials would be located above an appropriate design flood level, which would be determined based on the duration of the construction works.
9K	The following staging process would be considered to be implemented when constructing surface water drainage infrastructure: • Biofiltration and detention basins that form part of the proposed stormwater management strategy would be excavated at the first phase of development, with the intention that the excavated basins would be used as temporary construction phase sedimentation basins. Once these construction phases become operational, these temporary construction phase sedimentation basins could be developed into the permanent biofiltration and detention basins. • During the relevant phase of development, all major stormwater pipes and culverts (600 mm diameter and larger) and main channels and outlets would be installed. Minor drainage and upstream systems would then be progressively connected to the major drainage elements during each phase of construction as required.
9L	A soil and water management plan (or equivalent) would be developed before land was disturbed that would include erosion and sediment control plans (ESCPs) and procedures to manage and minimise potential environmental impacts associated with construction of the Project. The ESCP(s) for the Project would be prepared in accordance with Volume 1 of Managing Urban Stormwater: Soils and Construction ('the Blue Book') (Landcom 2004), Managing Urban Stormwater: Soils and Construction – Installation of Services, Volume 2A (OEH 2008) and Managing Urban Stormwater: Soils and Construction – Main Road Construction, Volume 2D (OEH 2008). The ESCP(s) would be established before the start of each construction phase and would be updated as relevant to the changing construction activities. Strategies to be considered as part of the plan include: • clean runoff from upstream undisturbed areas would be diverted around the Project site to minimise overland flow through the disturbed areas; • stabilised surfaces would be reinstated as quickly as practicable after construction;

REMM / MCoA No.	Mitigation measure
	 all stockpiled materials would be stored in bunded areas and away from waterways to avoid sediment-laden runoff entering the waterways;
	• sediment would be prevented from moving offsite and sediment- laden water prevented from entering any watercourse, drainage line or drainage inlet;
	 erosion and sediment control measures would be regularly inspected (particularly following rainfall events) to monitor their effectiveness and stability;
	erosion and sediment control measures would be left in place until the works are complete or areas are stabilised;
9M	Procedures to maintain acceptable water quality and to manage chemicals and hazardous materials (including spill management procedures, use of spill kits and procedures for refuelling and maintaining construction vehicles/equipment) would be implemented during construction.
9N	Vehicles and machinery would be properly maintained to minimise the risk of fuel/oil leaks.
90	Routine inspections of all construction vehicles and equipment would be undertaken for evidence of fuel/oil leaks.
9P	All fuels, chemicals and hazardous liquids would be stored within an impervious bunded area in accordance with Australian Standards and NSW Environment Protection Authority guidelines.
9Q	Emergency spill kits would be kept onsite at all times. All staff would be made aware of the location of the spill kits and trained in their use.
98	Construction plant, vehicles and equipment would be refuelled offsite, or in designated re-fuelling areas located at least 50 metres from drainage lines or waterways.

6 CONCLUSION

In summary, potential impacts on stormwater associated with the Modification Proposal represent a minor increase from those assessed for the Early Works under the MPW Concept Plan EIS, RtS and SRtS. Through the implementation of the mitigation measures approved for the MPW Concept Plan identified above, stormwater impacts associated with the Modification Proposal are expected to be consistent with the impacts predicted within the MPW Concept Plan EIS.

APPENDIX A DRAWINGS



MPW INTERMODAL TERMINAL FACILITY

MPW CONCEPT PLAN MODIFICATION SECTION 96

DRAWING LIST


GENERAL

MCPN-ARC-CV-DWG-0001 COVERSHEET AND DRAWING LIST

SITE PREPARATION MCPN-ARC-CV-DWG-0101

EROSION AND SEDIMENT CONTROL PLAN MCPN-ARC-CV-DWG-0106 EROSION AND SEDIMENT CONTROL DETAILS

MCPN-ARC-CV-DWG-0111 EARTHWORKS PLAN




LOCALITY PLAN 1:20,000

IMAGERY EXTRACTED FROM nearmap.com

DISCLAIMER THIS MAP HAS BEEN PREPARED USING nearmap.com IMAGERY. THIS DATA IS NOT GUARANTEED TO BE FREE FROM ERROR OR OMISSION. THEREFORE ARCADIS AND ITS EMPLOYEES DISCLAIM LIABILITY OF ANY ACT DONE OR OMISSION MADE ON THE INFORMATION CONTAINED IN THIS DATA AND ANY CONSEQUENCES OF SUCH ACTS OR OMISSIONS. THIS DRAWING IS PROVIDED FOR THE INFORMATION OF THE PERSON OR OR GOADISTION TO THIS DRAWING ARCADIS PROVIDES IT. IT MAY NOT BE PROVIDED TO, OR USED BY, ANY OTHER PERSON WITHOUT ARCADIS' PRIOR WRITTEN CONSENT.

02	DRAWING TITLE CHANGED	20.06.2016
01	ISSUE FOR INFORMATION	23.05.2016
Issue	Description	Date





Client	SIMTA SYDNEY INTERMODAL TERMINAL ALLIANCE
	TACTICAL

Status	PRELIMINARY ONLY NOT TO BE USED FOR CONSTRUCTION					
Scales		Current Issu	e Signatures			
	1: 20000	Drawn C.MABER				
Original Size	A1	Designed L.CORSCADDEN		Title		
Height Datum	AHD	Checked D.STONE				
Grid		Annroyed		1		

MPW INTERMODAL TERMINAL **FACILITY** MPW CONCEPT PLAN **MODIFICATION**

> COVER SHEET AND DRAWING LIST




Level 5, 141 Walker St NORTH SYDNEY NSW 2060 ABN 76 104 485 289 Tel No: +61 2 8907 9000


Fax No: +61 2 8907 9001 AA009335 arcadis.com


Project No.

Drawing No.


MCPN-ARC-CV-DWG-0001- 02








NOT TO SCALE



SD 6-4 EARTH BASIN - WET (APPLIES TO 'TYPE D' AND TYPE F' SOILS ONLY) NOT TO SCALE



STABILISED SITE ACCESS AND TRUCK WASH DOWN AREA (SD6-14) NOT TO SCALE

02	DRAWING TITLE CHANGED	20.06.2016
01	ISSUE FOR INFORMATION	23.05.2016
Issue	Description	Date
	100mm on Origin	al



Status NO	PRELIMINA OT TO BE USED F		Project MPW IN	TERMODAL TERMINAL FACILITY	
Scales	NOT TO COME	Current Issu	e Signatures	MPV	V CONCEPT PLAN
	NOT TO SCALE	Drawn C.MABER		<u> </u>	MODIFICATION
Original Size	A1	Designed L.CORSCADDEN		Γitle	
Height Datum	AHD	Checked D.STONE		EROS	ION AND SEDIMENT

Approved

CONTROL DETAILS



Level 5, 141 Walker St NORTH SYDNEY NSW 2060 ABN 76 104 485 289 Tel No: +61 2 8907 9000

Fax No: +61 2 8907 9001 arcadis.com


Drawing No. MCPN-ARC-CV-DWG-0106- 02

Project No.

AA009335

Filenam CPN-ARC-CV-DWG-0106-Erosion And Sediment Control Details.d

Date Plotted: 20 Jun 2016 - 08:23AM File Name: C:\SharePoint\AA009335 - Moorebank - 2_MCPN\CV\DWG\MCPN-ARC-CV-DWG-0106-ErosionAndSedimentControlDetails.dwg



APPENDIX B GEOTECHNICAL ADVICE



TECHNICAL MEMORANDUM

DATE 30 May 2016

DOCUMENT No. 1416224-027-Rev1

TO Nathan Cairney

CC Greg Stratton

FROM Nathan Steggles

EMAIL nsteggles@golder.com.au

GEOTECHNICAL AND CONTAMINATION MEMORANDUM SUPPORTING MPW CONCEPT PLAN/EARLY WORKS MODIFICATION FOR FILL IMPORTATION

1.0 INTRODUCTION

The Moorebank Intermodal Company (MIC) has received Concept Plan Approval, under Part 4, Division 4.1 of the *Environmental Planning and Assessment Act* 1979 (EP&A Act), to develop the Moorebank Precinct West Intermodal Terminal Project (MPW Project) on the western side of Moorebank Avenue, Moorebank, in south-western Sydney (the MPW site).

On 4 June 2015, the MIC, with the approval of the Commonwealth Government, entered an agreement with the Sydney Intermodal Terminal Alliance (SIMTA) under which SIMTA will obtain approvals, build and operate all stages of the MPW Project at Moorebank. SIMTA is seeking approval to modify the MPW Concept Proposal and Stage 1 (Early Works) approval (SSD_5066) (MPW Concept Plan Approval).

The Environmental Impact Assessment (EIS) prepared for the Concept Plan Approval identified that fill material required for the development of the MPW site would be largely sourced from excavations within the MPW site and hence imported fill volumes for the project would be relatively minor. Subsequent civil design development for the MPW Project has identified that fill required to be imported to the MPW site is estimated at 1,600,000 cubic metres (m³). It is proposed to undertake additional site preparatory works, including the import, placement and stockpiling of clean fill, as a modification to the approved Stage 1 (Early Works).

This Geotechnical and Contamination Memorandum has been prepared to support an application made under section (s) 96(2) of the EP&A Act to modify the MPW Concept Plan Approval (SSD_5066) to allow for the Modification Proposal. The Modification Proposal includes the importation, direct placement, compaction and stockpiling of a total of 1,600,000m3 of fill to the primary earthworks area. Figure 1 shows the location of the proposed Modification Proposal, including the area of impact and the primary earthworks area, where direct placement and stockpiling of material would be undertaken.

This memorandum has been prepared in accordance with the request (received from Nathan Cairney of Tactical, 20th April 2016) and our proposal of 22nd April 2016 (Ref: 1416224-026-P-Rev0).




Figure 1: Proposed earthworks (MPW Concept Plan Modification)



1.1 Purpose of this memorandum

This Geotechnical and Contamination Memo assessment report has been prepared to provide further information on, and environmental assessment of, the Modification Proposal. The Modification Proposal has been reviewed against the Secretary's Environmental Assessment Requirements (SEARs, SSD 5066) and documentation prepared for the MPW Concept Plan Approval and applicable legislation and guidelines to determine whether the works and associated impacts of the Modification Proposal are 'substantially the same development' as that proposed under the MPW Concept Plan Approval.

This memorandum highlights the geotechnical and contamination issues pertaining to the area of the proposed imported fill stockpile (primary earthworks area) and the anticipated impact of the proposed stockpile on the existing site conditions. The memorandum also addresses the development of the detail design of the stockpile material and arrangement.

2.0 EXISTING SITE CONDITIONS

The MPW Concept Plan Approval (<u>SSD 5066</u>1), includes conceptual approval to use the land held by MIC as an intermodal terminal, and to undertake "Early Works (Stage 1)". The NSW Department of Planning and Environment draft conditions of consent, defined the Early Works (Stage 1) as:

- removal of existing hardstand/roads/pavements and infrastructure associated with existing buildings including services termination and diversion
- rehabilitation of the excavation / earthmoving training area;
- remediation of contaminated land;
- removal of underground storage tanks;
- minor clearing and grubbing of the temporary stockpiling area
- heritage impact remediation works; and
- the establishment of construction facilities and access, including site security.

The primary earthworks area that is the area of proposed filling covers a variety of previous land-use. A large part of the area is grassed with scattered trees, occupied by low rise warehouses, administration and training buildings, and residential housing associated with the former Army School of Engineering (SME). Paved access roads, along with paved and unpaved open space and landscaped sporting fields occupy a large proportion of the site. A number of ponds are present in the north eastern corner of the proposed stockpile area. An existing stormwater system comprising pits, pipes and open channels runs through the area. However it is anticipated that these features will be removed, redirected and remediated as appropriate as part of the approved Early Works.

A summary of the geology, soils and contamination of the area and key geotechnical and contamination aspects of subsurface conditions, relating to the Modification Proposal are discussed below.

2.1 Geology

The published 1:100,000 Penrith Geological Map (NSW Department of Minerals, 1991) indicates that the area of impact is characterised by Tertiary alluvial deposits (Ta) of Pliocene age with terraces of more recent Quarternary (Holocene) age (<10,000 years) alluvial deposits (Qha) adjacent to the Georges River. The geological map indicates that the underlying rock conditions in the area are either Triassic Hawkesbury Sandstone (Rh) or Ashfield Shale (Rwa). A brief overview of the ground conditions encountered within the area of impact is provided below. Geological conditions at the MPW site are discussed in further detail in the Golder Geotechnical Interpretive Report (Ref. 147623070-011).



http://www.majorprojects.planning.nsw.gov.au/index.pl?action=view_job&job_id=5066

2.2 Soils

Outside of existing structures, a variety of paved and unpaved surfaces are present across the area of impact. In unpaved areas, the site is characterised by a relatively thin layer of predominantly granular topsoil, underlain by alluvial soils over bedrock. The topsoil thickness encountered during investigation varies up to approximately 0.2 m thickness but is typically 0.1 m thickness or less. The organic content varies but is typically minor. At selected investigation locations evidence of prior topsoil layers being filled over was observed. Locally thicker and more humic topsoil is to be expected in the immediate proximity of established vegetation (e.g. stands of trees and bushes). In some areas locally deep anthropogenic fill has been encountered up to 4 metres (m) deep (for detail reference can be made to the Golder Post Phase 2 ESA, Ref: 147623070-019, 2015).

In the primary earthworks areas, the natural alluvial material is a mixture of granular/sand (typically medium dense or denser) and cohesive/clay material (typically of very stiff consistency or harder). Cohesive alluvial material predominates over granular alluvial material, which is typically present as sand seams or bands within a clay profile. The depth to bedrock varies across the area typically in the range of 10m below ground surface to 25m below ground surface.

Following site preparation, in accordance with activities noted as being part of Early Works above, the foundation for filling is anticipated to typically include sand fill, clay fill, alluvial clay and alluvial sand. As discussed in the Golder Geotechnical Interpretive Report (Ref: 147623070-11), significantly different performance can be expected between the granular (i.e. sand) and cohesive (i.e. clay) material as a subgrade/stockpile foundation (i.e. differing soaked CBR values and swell potential). Differing performance is also likely between the alluvial and fill material of similar grain size (e.g. both clay or both sand), although to a lesser degree.

The exception to this is the anthropogenic fill which due to the nature of its placement (inferred to be uncontrolled) and inclusions (such as timber, steel and concrete building debris and general rubbish) will typically not be suitable as a foundation in its current condition.

Due to historic site use, the lateral extent of fill will vary at similar elevations. Likewise sand seams and bands within the dominantly clay alluvium will be laterally discontinuous. Delineation of zones of granular versus cohesive subgrade may prove difficult, even with relatively extensive investigation, prior to stripping and exposure of subgrade.

Foundation preparation requirements will be addressed in the site specific Earthworks Specification (the Earthworks Specification) as discussed further in Section 3.0 of this memorandum.

2.3 Groundwater

Groundwater beneath the primary earthworks areas has been recorded as typically between 9 to 12m below existing ground surface (i.e. approximately RL 2m to RL 6m) and flowing towards the Georges River (west). This was broadly corroborated by the recent Stage 2, 2016 investigation undertaken by Golder Associates except at GA-TP-3112 which recorded groundwater inflow at 2.9m below ground surface. This was inferred to be a local effect resulting from the proximity of an existing pond.

The impact of the proposed stockpile on groundwater levels will be dependent on numerous factors including the manner in which the foundation of the stockpile is prepared, the nature of the stockpile material and surface drainage provided within and around the stockpile. We note that ongoing groundwater monitoring is expected as part of the long term environmental management plan. More detailed assessment of groundwater impacts may be appropriate dependent on the duration of the proposed temporary stockpiling and the level of sensitivity of the management measures for groundwater risk to fluctuations in groundwater level.

2.4 Contamination

The contamination on the site has been subject to numerous investigations with the most current investigation documents included in the MPW Concept Plan EIS. These included the Phase 1 and Phase 2 Environmental Site Assessment Reports and the provisional Remediation Action Plan (RAP), prepared by PB in 2014, and the Post Phase 2 Environmental Site Assessment Report and Validation Plan - Principals prepared by Golder Associates in 2015.



Subsequently as part of the Early Works, the site will be remediated to the extent permissible under the MPW Concept Plan Approval (SSD - 5066). These remediation works will be audited by an accredited contaminated land Auditor, and that the Auditor will prepare a section A, Site Audit Statement at the completion of the remediation works. The Site Audit Statement will be provided to the consent authority to satisfy the obligations under Clause 7(1) of State Environmental Planning Policy 55 and the MPW Concept Plan Approval Minister's Conditions of Approval (MCoA) B1 to B3.

2.4.1 Early Works Remediation

The remediation to be completed under the Early Works will include:

- the demolition, excavation and remediation of known underground storage infrastructure and associated contaminated soils impacted with petroleum hydrocarbons;
- the excavation and remediation of known stockpiles of building demolition waste and/or asbestos contaminated soils:
- the excavation and remediation of known areas of soil contamination ('hotspots') including soils impacted with lead, and petroleum hydrocarbons at concentrations which present an unacceptable risk to the future use of the site;
- the assessment and if required remediation of materials suspected of being contaminated with polychlorinated bi-phenols (PCBs), organochlorine pesticides (OCP) and per- and poly-fluorinated alkyl substances (PFAS); and
- the assessment and if required remediation of underground utilities suspected as either being made of or suspected of containing hazardous or contaminated materials.

The remediation and validation works will be completed in accordance with the guidelines endorsed by the NSW Environmental Protection Authority (EPA) under Section 105 of the *Contamination Land Management Act* 1997 (CLM Act).

The NSW EPA's preferred position on the selection of remediation options, as stated in the DEC, NSW (2006) *Auditor Guidelines*, is to preference on-site treatment of the soil so that the level of contaminant is either destroyed or the associated hazard is reduced to an acceptable level ahead other remediation options. Onsite treatment is applicable for the identified hydrocarbon contaminants which are amenable to onsite biological treatment through land farming. However, recalcitrant contaminants such as heavy metals and asbestos are often not amenable to onsite treatment, and alternative options such as excavation and isolation, excavation and disposal, or leaving contaminated material in situ with management controls are appropriate options for consideration. This prioritisation is supported by the NSW EPA Waste Avoidance and Resource Recovery Strategy [WARR] (EPA 2014), which adopts the waste minimisation hierarchy and is aimed at avoiding and reducing the generation of waste.

The remediation works will include the preparation of documents expected to be required to facilitate the progression of the remediation and ensure appropriate mitigation measures are implemented during the future development of the site:

- Stage specific Remediation Action Plans (RAPs) a RAP specific to each stage of development will be required to accommodate the detailed engineering design within the adopted remedial approaches, as well as to align with the staged development approval process. The stage specific RAPs are to refer to the Preliminary RAP (PB, 2014b), and the Site Validation Principles (Golder, 2015c) and are to include validation plans appropriate for each proposed stage of development which includes remediation actions.
- Stage specific Remediation and Validation Reports (RVR) at the appropriate time and where required, a RVR will be prepared for each development area. These reports will document the remediation and validation activities completed within a specific area. These reports will facilitate the Auditor's review of the remediation and validation activities;
- Construction Environmental Management Plan (CEMP) a CEMP will be developed specific to each stage of development, and where required the CEMP will draw on the requirements of MCoA D19, the



processes described in the Preliminary RAP (PB, 2014a), the Validation Plan - Principles and the Remediation Specification (Golder 2015c), as well as the Stage Specific RAP developed for that stage of the MPW Project. The CEMP will also stipulate the actions to be taken should additional contamination be identified during the development of the site (i.e. an unexpected finds protocol).

- EOW and UXO Management Plan a site wide, and/or stage specific EOW/UXO Management Plan will need to be developed as part of the CEMP to ensure a safe working environment is established during earthworks.
- Asbestos in Soils Management Plan (AMP) the AMP will be prepared to specifically address the management of asbestos in or on soils during the remediation and staged development of the site. The AMP will define the actions, roles and responsibilities associated with the management of asbestos in or on soils during the proposed development works. Any management or remediation actions undertaken in relation to asbestos in soils will be undertaken in accordance with the Safe Work NSW requirements, including but not limited to the guidelines for Managing asbestos in or on soil (2014), and Codes of Practice How to Safely Remove Asbestos (2011) and How to Manage and Control Asbestos in the Workplace (2011). Asbestos works will also be undertaken by appropriately trained persons including those with Class A licences for the removal of friable asbestos and / or Class B licences for the removal of non-friable asbestos. The remediation and/or management actions will include:
 - Onsite in-situ containment through the direct placement of cover fill materials to prevent future disturbance of the impacted materials and therefore minimise the potential for the materials to generate airborne fibres. The cover will be nominally minimum 0.5 meters (m) depth. However, in areas where the final design require less than 0.5m of cover, visible ACM fragments will be removed and the area nominated for closer management within the Long Term Environmental Management Plan;
 - Onsite excavation and containment through the excavation and replacement of asbestos impacted soils in a nominated containment area. The onsite containment areas will be nominated in consultation with the appointed Site Auditor, will consider positions on the site which present minimal impact to the proposed development and minimise the potential for disturbance during the future operation of the site. Containment will include the placement of materials at depths generally greater than 1.5m, and will include a minimum of 0.5 m cover to minimise the potential for the materials to generate air borne fibres. Onsite containment locations will be mapped and noted for closer management within the Long Term Environmental Plan;
 - Excavation and offsite disposal through the excavation, transport and offsite disposal of soils impacted with asbestos. Excavation works will be completed at areas where impacted soils are not considered suitable or onsite insitu containment, or are unsuitable for inclusion within an onsite containment area. Excavated materials will be disposed of in accordance with the requirements of the Waste Management Plan, and will be disposed at a facility appropriately licenced by the NSW EPA for the receipt of friable asbestos wastes.

The AMP will include general requirements for the management of asbestos works including consultation requirements, licencing requirements, health monitoring and air monitoring requirements. The AMP will also include protocols for un-expected finds of asbestos during future development earth works. It is expected that where warranted the AMP will be updated and reissued at the completion of the Early Works remediation activities, and as each stage of development is completed.

Long Term Environmental Management Plan (LTEMP), a site wide LTEMP will be developed at the completion of the remediation works and will prescribe the protocols for the ongoing maintenance and /or monitoring or any long term remedial or mitigation measures implemented during the remediation. The LTEMP will include the roles and responsibilities for implementation, the consultation requirements, and licencing requirements. The LTEMP will stipulate the actions to be taken should additional contamination be identified during the post development occupation of the site (i.e. an unexpected finds protocol, an asbestos in soils response plan and UXO/EOW response plan). It is expected that where warranted the LTEMP will be updated and reissued as each stage of development is completed.



3.0 MODIFICATION WORKS

It is proposed to undertake additional site preparatory works, including the import, placement and stockpiling of clean fill, as a modification to the approved Early Works. The proposed modification would result in an intensification of activity associated with the approved Early Works. The works, for which a modification is sought (the Modification Proposal), include the following:

- Minor vegetation removal (not Endangered Ecological Communities, slightly above that provided within Early Works)
- Import, by truck, of approximately 1,600,000m³ of fill (from offsite locations)
- Stripping and stockpiling of topsoil within the area of impact, cut and fill (within the primary earthworks areas) and stockpiling of clean fill within the primary earthworks areas (see Figure 1)
- Temporary sediment and erosion control works, including onsite detention basins (greater than those envisaged within the Early Works)
- Establishment of temporary internal haulage routes, construction compounds (including, but not limited to, a materials crusher and other plant and equipment) (additional to those included within Early Works).

Figure 1, above, shows the location and extent of the Modification Proposal, which would occur largely within the footprint of the approved Early Works.

3.1 Earthworks

The nature of the fill to be imported for permanent placement and stockpiling is understood to be a clean, non-expansive, sandstone fill, in general accordance with a material derived from the sandstone bedrock indicated in borehole logs LDS-BH-1042 and LDS-BH-1050 (Attachment 1). The stockpile layout is shown in the Earthworks Plan (Drawing No. MCPN-ARC-CV-DWG-0111, Issue 01), provided as Attachment 2.

The materials are likely to be sourced form a local Sydney tunnel that is to be excavated with road headers, producing a spoil mix comprising sands, gravels and cobbles. Some fine grained materials will also be present but are expected to make up less than 10% by weight. Dependent on the grading of the as received material some processing (possibly screening only or crushing and screening) will be required to provide a material suitable for permanent placement in accordance with the Earthworks Specification.

In general the material would also need to be equivalent to Class 1 or 2 materials (i.e. compliant with the NSW EPA definitions of Virgin Excavated Natural Materials or Excavated Natural Materials) as discussed in the in the Validation Plan – Principles (Golder, 2015) and as included in the MPW Concept Plan application. To be compliant with the above mentioned definitions, consideration will also be given to the potential for acid rock conditions within potential fill sources and dependent on the material source (and its variability) laboratory testing for acid rock conditions will be completed.

Furthermore, the importation and placement of permanent fill will need to conform to the project Earthworks Specification, which is yet to be developed. The Earthworks Specification will include details on earthworks material criteria, handling and placement requirements, embankment and cutting formation (including foundation, batter and benching requirements), unsuitable material and bridging layer requirements, conformance testing methods and acceptance criteria (e.g. for material acceptance and compaction control). It is noted that for the upper zone of the permanently placed fill (which may form subgrade to pavement or foundation to structures) particular requirements will exist to mitigate against, for example, stress concentrations around cobble sized material underlying pad footings.

Permanent fill and the overlying temporary stockpile will be derived from material which performs as an earthfill rather than a rockfill. Meaning, the fill should be constructed such that its strength and stability are obtained from compaction of finer material (dominantly sand grain size), embedding larger rock pieces (to the maximum particle size and in proportions satisfying the requirements of the project Earthworks Specification) rather than mechanical interlock (as might apply in a rock fill embankment). The material



grading adopted within the Earthworks Specification for imported sandstone should be such that validation testing of compaction is possible by conventional methods. This will require that rock material is sufficiently broken down and evenly distributed through the fill material, with sufficient finer material surrounding to produce, dense, compact fill layer to the project Earthwork Specification requirements.

Laboratory testing of proposed imported fill material should be undertaken to confirm suitability in accordance with the project Earthworks Specification. In view of the sandstone fill proposed for importation such testing, for material intended for permanent placement will include:

- Laboratory compaction testing
- Soaked CBR testing (with prior pre-treatment in accordance with RMS T102 and T103)
- Particle Size Distribution (as received and post pre-treatment in accordance with RMS T102 and T103)
- Atterberg Limit Testing.

3.2 Direct placement of fill

Direct placement of fill will require foundation preparation in accordance with the project Earthworks Specification. In general foundation preparation will typically involve clearing and grubbing, grading, levelling, moisture conditioning and compaction of an upper zone of the subgrade. General clearing should include removal of everything on or above the site surface, including rubbish, vegetable matter and organic debris, scrub, trees, timber, stumps, boulders and rubble, slabs, foundations, retaining walls, paving, abandoned services and the like. Before commencing foundation preparation any infrastructure (e.g. relocated services) will be located, marked and documented in the areas that will be affected by the earthworks operations. It is noted that poorly documented infrastructure locations could present a significant risk to future development, particularly should deep foundations be required.

Due to the variable nature and depth of 'topsoil', assessment will be made in accordance with the Earthworks specification as to the appropriate depth of topsoil stripping at specific locations. Scalping of vegetation (e.g. grass cover) will be necessary as part of general grading and preparation for filling. Some localised areas free of topsoil will likely be encountered based on the proposed footprint of stockpiling. In other areas locally deeper topsoil will be encountered (e.g. within zones of established vegetation). Final depths of topsoil stripping will be determined in accordance with the Earthworks Specification. However, for planning purposes an average allowance of 0.1 m of topsoil stripping is made.

Provision for addressing unforeseen zones of 'unsuitable' material will be addressed within the Earthworks Specification. It is noted that higher compaction requirements are likely to be required for the foundation and direct placed fill itself than may be acceptable for the temporary fill stockpile. There is potential for ACM and EOW /UXO to be encountered during topsoil stripping and this will be managed in accordance with the Asbestos in Soil Management Plan and EOW/UXO Management Plan.

The height of areas of direct placed fill is understood to vary, general comments on management of surface water, potential scour, slope stability and protection from fouling with vegetation provided in Section 3.3 apply also to the lower portion of placed fill intended to be left in place permanently.

3.3 Stockpiling of fill

Stockpiles will be placed and compacted in accordance with the Earthworks Specification. Adequate compaction will be required to achieve necessary stability, mitigate against erosion and provide a sufficiently trafficable surface to enable maintenance and inspection. However, compaction requirements for the stockpile material will likely be less than that for permanent fill placement.

Compaction requirements adopted in the Earthworks Specification should be developed in consideration of the intended life of the stockpile (i.e. how long it will be in place) and performance requirements including accessibility. As a preliminary guide, a relative compaction of 90% Standard Maximum Dry Density (SMDD) will likely be acceptable for temporary stockpiles. A higher level of compaction will be considered if proposed batter slope angles or vehicle loading necessitate it. Consideration will also be given to the allowable proximity of plant and equipment to the crest/edge of the temporary stockpile.



The Earthworks Plan, (Drawing No. MCPN-ARC-CV-DWG-0111, Issue 01), provided as Attachment 2, indicates a stockpile height of 6m with batter slopes of 1V:3H. Adequate stability is likely to be readily achievable for an imported sandstone product such as could be produced from the sandstone bedrock shown on the provided borehole logs, when adequately compacted. Maximum batter slope limits should be provided in the Earthworks Specification but would likely be limited to 1V:2H for temporary stockpiles. This steeper slope angle (than the 1V:3H indicated in the provided drawing) should be readily achievable for an adequately compacted sandstone fill. However, it is noted that shallower slopes may be suitable in consideration of potential maintenance and access requirements (particularly so for the base of the stockpile which will be left as a permanent feature).

For heights greater than 4m, benching will be implemented. A bench will also be incorporated at the top of the permanent fill placement such that some flexibility exists in the maximum height of the temporary fill batter above. This may also present an advantage in installation of erosion protection and drainage measures as discussed below. The bench height will be set above finished level for permanent placement, such that "fouling" of the near surface of the bench, during operation of the temporary stockpile, could be addressed by stripping an upper zone (say 1 to 2 lifts up to 500mm) off the zone of the perimeter bench at the time of removal of the overlying stockpile.

To maintain trafficability and manage surface water, the temporary stockpile will be graded and potentially provided with a temporary surfacing in some or all areas dependent on access requirements and usage. The surfacing appropriate will be dependent on the nature of the imported fill adopted and the access and usage requirements of the stockpile. In view of this, surfacing may be restricted to provision of (zones) of spray polymer or durable inert crushed rock (e.g. 'blue metal'). If high quality imported fill is obtained and/or frequent access to and usage of the surface of the stockpile is not required it may not be necessary to provide any surfacing.

The potential for fouling of the upper lifts(s) of the stockpile with vegetation will be addressed in the Earthworks Specification and in consideration of appropriate surfacing. It is noted that, given the large areal extent of the stockpile, unintended spread of vegetation (e.g. grasses) within unprotected surfaces could result in the need for treatment of a large volume of otherwise 'ready to place' material.

If considered appropriate, a grass cover will be established over the lower portion of the fill, intended as permanent placement early on, to manage erosion and surface flow issues associated with the overlying temporary stockpile. A bench at the approximate interface between the permanent and temporary filling (as described above) would also have the advantage of separating these zones with different batter slope protection measures.

Temporary erosion and sediment control measures will be required for the stockpile and will include the installation of crest drains and batter chute drains, as required. These will be detailed within a Sediment and Erosion Control Plan prepared in accordance with the requirements of the Landcom, Soils and Construction, Managing Urban Stormwater Volume 1 4th Edition, March 2004.

The magnitude of surface drainage measures will be developed based upon suitable hydrological assumptions pertinent to the site. The sophistication and durability of the drainage measures will be developed in consideration of the intended life of the stockpile. However, the impact of the surface drainage elements adopted on the permanent fill placement below will also be considered. For example, appropriate frequency of chute drains and what level of energy dissipation might be appropriate. Seeding of a lower permanent batter should provide protection against scour and erosion. Mitigation of the grass spreading into the overlying temporary batter and (potentially fouling the materials) would be aided by physical separation with a bench at the approximate boundary of the permanent fill materials and temporary stockpiles materials and might be addressed by spraying with an acceptable herbicides.

4.0 CONCLUSION

Importation of sandstone fill presents a number of benefits for the management of asbestos contamination, potential UXO/EOW and subgrade performance issues. Management of quality control aspects of the permanent fill and risks associated with temporary stockpiling should be addressed by a site specific earthworks specification (the Earthworks Specification) developed in consideration of the final design layout adopted and operational requirements relating to the stockpiling during construction stage.



Key geotechnical and contamination benefits resulting from the importation of non-expansive sandstone fill meeting the Earthworks Specification requirements are:

- Provision of a more consistent less moisture sensitive working platform
- Provision of a laterally consistent layer for which pavement design can be developed consistently over large areal extents (where appropriate to design loads and operational requirements), with possible economy in pavement design
- Possible economy in pavement design due to potentially higher CBR values being achievable for the imported fill than existing site material (dependent on the actual level of subgrade, resulting from design fill heights and pavement thicknesses)
- Potential improvement of foundation performance via "pre-loading" effect of the temporary stockpile

In summary, impacts on geotechnical considerations within the area of impact associated with the Modification Proposal constitute a small change from those assessed for the Early Works under the MPW Concept Plan EIS, Response to Submissions (RtS) and Supplementary Response to Submissions (SRtS). Through the implementation of the mitigation measures approved for the MPW Concept Plan and the RMCoA, impacts associated with the Modification Proposal are expected to be consistent with the impacts predicted within the MPW Concept Plan EIS.

The recommended mitigation measures include the development and implementation of the following, in accordance with the MPW Concept Plan Approval and supporting documentation:

- Earthworks Specification
- Sediment and Erosion Control Plan
- Construction Environmental Management Plan (CEMP)
- EOW and UXO Management Plan
- Asbestos in Soils Management Plan (AMP); and
- Long Term Environmental Management Plan (LTEMP).

5.0 CLOSURE

We trust this memorandum provides sufficient input to your supporting memorandum as requested. If you have any questions, please do not hesitate to contact the undersigned in our Sydney Office.

Attachments:

Attachment 1 - Borehole Logs provided by client

Attachment 2 - Earthworks Plan, Drawing No. MCPN-ARC-CV-DWG-0111, Issue 01, Arcadis

Nathan Steggles Greg Stratton

Senior Geotechnical Engineer Principal Environmental Engineer

NRS/GVS:BJF/nrs



Limitations

This Document has been provided by Golder Associates Pty Ltd ("Golder") subject to the following limitations:

This Document has been prepared for the particular purpose outlined in Golder's proposal and no responsibility is accepted for the use of this Document, in whole or in part, in other contexts or for any other purpose. The current issue of this document is Draft for discussion only and is subject to finalisation which may include alteration of the comments provided herein.

The scope and the period of Golder's Services are as described in Golder's proposal, and are subject to restrictions and limitations. Golder did not perform a complete assessment of all possible conditions or circumstances that may exist at the site referenced in the Document. If a service is not expressly indicated, do not assume it has been provided. If a matter is not addressed, do not assume that any determination has been made by Golder in regards to it.

Conditions may exist which were undetectable given the limited nature of the enquiry Golder was retained to undertake with respect to the site. Variations in conditions may occur between investigatory locations, and there may be special conditions pertaining to the site which have not been revealed by the investigation and which have not therefore been taken into account in the Document. Accordingly, additional studies and actions may be required.

In addition, it is recognised that the passage of time affects the information and assessment provided in this Document. Golder's opinions are based upon information that existed at the time of the production of the Document. It is understood that the Services provided allowed Golder to form no more than an opinion of the actual conditions of the site at the time the site was visited and cannot be used to assess the effect of any subsequent changes in the quality of the site, or its surroundings, or any laws or regulations.

Any assessments made in this Document are based on the conditions indicated from published sources and the investigation described. No warranty is included, either express or implied, that the actual conditions will conform exactly to the assessments contained in this Document.

Where data supplied by the client or other external sources, including previous site investigation data, have been used, it has been assumed that the information is correct unless otherwise stated. No responsibility is accepted by Golder for incomplete or inaccurate data supplied by others.

Golder may have retained subconsultants affiliated with Golder to provide Services for the benefit of Golder. To the maximum extent allowed by law, the Client acknowledges and agrees it will not have any direct legal recourse to, and waives any claim, demand, or cause of action against, Golder's affiliated companies, and their employees, officers and directors.

j:\geo\2014\1416224_simta_stage 1_moorebank\correspondence out\1416224_027_rev1_supporting memo for MPW Concept Plan modification.docx



Attachment 1 – Borehole Logs





REVISION C REPORT OF BOREHOLE: LDS-BH-1042

CLIENT: CDSJV COORDS: 329653.0 m E 6243541.0 m N MGA94 56

PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90°

JOB NO: 1524285 HOLE DEPTH: 90.00 m

SHEET: 1 OF 10 REV: C
DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15

LOGGED: MHA/JN DATE: 23/12/19
CHECKED: GMcN DATE: 8/1/16

Ľ	JOB N	IO:	15242	85				HOI	LE DEPTH: 90.00 m	(CHEC	KED: GMcN	DATE: 8/1/1	6	
		Dril	lling		Sampling				Field Material Desc						
METHOD	PENETRATION	WATER	DEPTH (metres)	<i>DEPTH</i> RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE	CONSISTENCY DENSITY	STRUCTUR ADDITIO OBSERVA	NAL	TINO	
0.0 LIB FOR NSW GLB Log GAP NON-CORED FULL PAGE 1524285 MASTER.GPJ < <drawngfile>> 04/03/2016 16:13 8.30,004 Datgel Tools NAID</drawngfile>	L L		0	1.35 0.70 0.70 0.70 -2.70 4.40 -3.00 4.85 -3.45 5.30 -3.90	DS 3.00-4.10 m drill cuttings DS 4.10-4.40 m drill cuttings SPT 4.40-4.85 m 2, 7, 11 N=18	X		SM SM CI-CH SM	ASPHALT (dark grey) FILL: Sandy GRAVEL yellow, with some bricks Silty SAND fine to medium grained, grey Silty SAND fine to medium grained. dark grey, weakly cemented Silty SAND fine to medium grained Sandy CLAY medium to high plasticity, dark brown, fine grained sand Silty SAND medium grained, pale grey	M	VL - VD MD S-F	No sampling or testing 28.09 m depth	g from 4.85 m to	Quatemary	

This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F01a




REVISION C REPORT OF BOREHOLE: LDS-BH-1042

COORDS: 329653.0 m E 6243541.0 m N MGA94 56 CLIENT: CDSJV

PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 2 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16



This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F01a RL3



REVISION C REPORT OF BOREHOLE: LDS-BH-1042

CLIENT: CDSJV COORDS: 329653.0 m E 6243541.0 m N MGA94 56

PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90°

JOB NO: 1524285 HOLE DEPTH: 90.00 m

SHEET: 3 OF 10 REV: C
DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16

													=	=
		Dril	ling		Sampling				Field Material Desc				_	_
МЕТНОБ	PENETRATION RESISTANCE	WATER	DEPTH (metres)	<i>DEPTH</i> RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE	CONSISTENCY	STRUCTURE AND ADDITIONAL OBSERVATIONS	LINI	
		T	20 —	<u>20.20</u> -18.80				CI- CH SP- SC	CLAY medium to high plasticity SAND		S-F L- MD			
	L		22 —	21.50 21.70 -20.30 22.00 22.20 -20.80				CH SP-SC CH SP	CLAY medium to high plasticity SAND CLAY medium to high plasticity SAND		S-F L- MD S-F		Quaternary	
			23 —	24 00							L - MD			
WB			24 — 25 —	-24.00 -22.60				CI- CH	Sandy CLAY medium to high plasticity, brown, fine grained sand					_
	н		26 —								St - VSt		Residual	
			27 — - - -											
			28 —						For Continuation Refer to Sheet 4					
			29 —											

This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F01a



CLIENT: COORDS: 329653.0 m E 6243541.0 m N MGA94 56


PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 4 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16

GAP gINT FN. F02a

RL3





CLIENT: COORDS: 329653.0 m E 6243541.0 m N MGA94 56


PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 5 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16

GAP gINT FN. F02a

RL3






CLIENT: COORDS: 329653.0 m E 6243541.0 m N MGA94 56

PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 6 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16



This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F02a



CLIENT: COORDS: 329653.0 m E 6243541.0 m N MGA94 56


PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 7 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16

GAP gINT FN. F02a

RL3






CLIENT: COORDS: 329653.0 m E 6243541.0 m N MGA94 56

PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 8 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16

RL3





CLIENT: COORDS: 329653.0 m E 6243541.0 m N MGA94 56


PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 9 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 DATE: 8/1/16 CHECKED: GMcN

GAP gINT FN. F02a

RL3





COORDS: 329653.0 m E 6243541.0 m N MGA94 56


CLIENT: PROJECT: WestConnex - The New M5 SURFACE RL: 1.4 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 90.00 m SHEET: 10 OF 10 REV: C DRILL RIG: Hydrapower Scout

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MHA/JN DATE: 23/12/15 CHECKED: GMcN DATE: 8/1/16

GAP gINT FN. F02a

RL3





CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GricTbi GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ «ChrawingFile»> 04/03/2016 16:14 8.30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285

COORDS: 329653.0 m E 6243541.0 m N MGA94 56

SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 90.00 m SHEET: 1 OF 8 REV: C DRILL RIG: Hydrapower Scout







CLIENT: CDSJV

GAP 8.10.0 LIB FOR NSW GLB GricTbi GAP CORE PHOTO 2 PER PAGE 1524285 MASTER GPJ <-DrawingFile>> 04/03/2016 16:14 8:30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway
JOB NO: 1524285

COORDS: 329653.0 m E 6243541.0 m N MGA94 56

SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 90.00 m SHEET: 2 OF 8 REV: C
DRILL RIG: Hydrapower Scout







CLIENT: CDSJV

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329653.0 m E 6243541.0 m N MGA94 56

SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 90.00 m SHEET: 3 OF 8 REV: C
DRILL RIG: Hydrapower Scout







CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GrCTbI GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ <<DrawingFile>> 04/03/2016 16:14 8:30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329653.0 m E 6243541.0 m N MGA94 56

SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 90.00 m SHEET: 4 OF 8 REV: C
DRILL RIG: Hydrapower Scout







CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GricTbi GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ «ChrawingFile»> 04/03/2016 16:14 8.30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329653.0 m E 6243541.0 m N MGA94 56

SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 90.00 m SHEET: 5 OF 8 REV: C
DRILL RIG: Hydrapower Scout







CLIENT: CDSJV

COORDS: 329653.0 m E 6243541.0 m N MGA94 56

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90°

HOLE DEPTH: 90.00 m

SHEET: 6 OF 8 REV: C
DRILL RIG: Hydrapower Scout







CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GrCTbI GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ <<DrawingFile>> 04/03/2016 16:15 8:30.004 Datgel Tools

SJV COORDS: 329653.0 m E 62

PROJECT: WestConnex - The New M5 LOCATION: M5 East Motorway

JOB NO: 1524285

COORDS: 329653.0 m E 6243541.0 m N MGA94 56

SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 90.00 m SHEET: 7 OF 8 REV: C
DRILL RIG: Hydrapower Scout







CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GricTbi GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ «ChrawingFile»> 04/03/2016 16:15 8.30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329653.0 m E 6243541.0 m N MGA94 56

SURFACE RL: 1.4 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 90.00 m SHEET: 8 OF 8 REV: C
DRILL RIG: Hydrapower Scout







CLIENT: CDSJV COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SHEET: 1 OF 10 REV: C
DRILL RIG: Hydropower

SURFACE RL: 1.7 m DATUM: AHD

CONTRACTOR: Hagstrom Drilling Pty Ltd

LOCATION: M5 East Motorway
JOB NO: 1524285

PROJECT: WestConnex - The New M5

INCLINATION: -90° LOGGED: MBB DATE: 7/1/16
HOLE DEPTH: 87.00 m CHECKED: GMcN DATE: 20/1/16

	Dril	lling		Sampling				Field Material Desc	riptio	n		
METHOD PENETRATION RESISTANCE	_	DEPTH (metres)	<i>DEPTH</i> RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	. 	CONSISTENCY DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS	LINIT
L-M			1.73 0.20 1.53 0.60 1.13 1.10 0.63 1.30 0.43 1.50				CI CH SM	TOPSOIL: CLAY medium plasticity, dark brown FILL: Sandy CLAY high plasticity, orange red, fine to medium grained, sub-angular sand FILL: Silty SAND medium grained, sub-rounded, dark grey, trace silt FILL: Gravelly SAND medium grained, dark grey, trace sub-rounded gravel	М	S F		E
L		- 2 - - -	0.23 1.75 -0.02	SPT 1.50-1.95 m 2, 3, 3 N=6			SP	FILL: SAND medium grained, sub-rounded to sub-angular, pale grey SAND medium grained, sub-rounded, pale brown, trace sub-angular gravel, with some shell fragments medium grained, sub-rounded, grey, with some shell fragments		L		
		3 — - - - 4 — -	3.00	SPT 3.00-3.45 m HW/450mm				fine grained, rounded, with some organic plant material		VL		
WB		5 — - - - -	4.50	SPT 4.50-4.95 m 5, 10, 15 N=25				fine to medium grained, rounded, pale grey				Quaternary
М		6 — - - - 7 —		SPT 6.00-6.45 m 12, 15, 13 N=28						MD		
		- - 8— - -	7.70	SPT 7.50-7.95 m 2, 1, 2 N=3			SC	Clayey SAND fine to medium grained, dark grey, low plasticity clay		L		
L		9 — - - -	9.30	U75 9.00-9.40 m PP = 50 kPa SPT 9.40-9.85 m 2, 3, 4 N=7			CH	Sandy CLAY high plasticity, pale grey, fine to medium grained sand		F		

This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F01a



COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SHEET: 2 OF 10

DRILL RIG: Hydropower

PROJECT: WestConnex - The New M5 LOCATION: M5 East Motorway

CLIENT:

04/03/2016 16:24 8:30:004 Datgel

1524285 MASTER.GPJ

SURFACE RL: 1.7 m DATUM: AHD

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MBB DATE: 7/1/16

REV: C

INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 87.00 m

CHECKED: GMcN DATE: 20/1/16 Drilling Sampling **Field Material Description** MOISTURE CONDITION CONSISTENCY DENSITY USCS SYMBOL RECOVERED STRUCTURE AND SAMPLE OR GRAPHIC LOG ADDITIONAL OBSERVATIONS SOIL/ROCK MATERIAL DESCRIPTION WATER DEPTH (metres) FIELD TEST H DEPTH RL 10 Sandy CLAY high plasticity, pale grey, fine to medium grained sand SPT 10.50-10.95 m 3. 5. 12 N=17 Casing dropped @ 10.80 m 11 VSt U75 11.00-11.40 m 12.00 -10.27 Organic material throughout, peat inferred SPT 12.00-12.45 m dark grey to black St 2, 3, 8 N=11 М Clayey SAND medium to coarse grained, sub-rounded to sub-angular, pale SC grey, with dark grey to black clay nodules 13 MD SPT 13.50-13.95 m 13.89 -12.16 Interbedded Clayey SILT and SAND medium plasticity, dark grey to black, clayey silt with trace fine grained gravel/charcoal, medium to coarse grained, sub-rounded, pale grey sand MI 14 14.50 -12.77 SAND medium to coarse grained, sub-rounded, pale grey L Quaternary WB 15 SPT 15.00-15.45 m 0, 0, 9 N=9 Interbedded CLAY and SAND high plasticity, grey, medium to coarse grained sand, apel grey St 16 SPT 16.50-16.95 m 9, 15, 18 N=33 17 SAND medium to coarse grained, sub-rounded, pale grey М GAP 8_10.0 LIB FOR NSW.GLB Log GAP NON-CORED FULL PAGE 18 SPT 18.00-18.45 m 2, 1, 6 N=7 19 MD SPT 19.50-19.95 m 1, 2, 11 N=13

This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F01a RL3



COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SHEET: 3 OF 10

DRILL RIG: Hydropower

PROJECT: WestConnex - The New M5 LOCATION: M5 East Motorway

SURFACE RL: 1.7 m DATUM: AHD

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MBB DATE: 7/1/16

REV: C

 LOCATION:
 M5 East Motorway
 INCLINATION: -90°

 JOB NO:
 1524285
 HOLE DEPTH: 87.00 m

CHECKED: GMcN DATE: 20/1/16

OB NO.		CKED: GIVICN DATE: 20/1/	
PENETRATION RESISTANCE	SAMPLE OR LIFE ON LIFE	STRUCTURE AND ADDITIONAL OBSERVATIONS	LIND
L	20 20 SAND medium to coarse grained, sub-rounded, pale grey coarse grained		
	21— 21.20 -19.47 SPT 21.00-21.45 m 5, 3, 6 N=9 CH CLAY high plasticity, brown-grey, with some fine to medium grained sand, with some black silts (possibly peat bands) PP = 250 kPa		
М	22— - 22.50 VSt		
	23 — U75 22.95-23.35 m PP = 300 kPa	Only pushed 0.19 m due to ground being too hard to continue for SPT	
	23.55 -21.82 24 - SPT 24.00-24.45 m 9, 10, 13 N=23 - SPT 24.00-24.45 m 9, 10, 13 N=23		
	25— SPT 25.50-25.95 m		Quaternary
	SPT 25.50-25.95 m 8, 11, 14 N=25		
н	27— SPT 27.00-27.45 m 9, 13, 9 N=22		
	28 - CL Sandy CLAY low plasticity, pale grey, fine to medium grained sand, trace coarse grained sub-angular gravel		
	SPT 28.50-28.95 m 8, 16, 22 N=38 SPT 28.50-28.95 m 8, 16, 22 N=38 SPT 28.50-28.95 m SP SAND coarse grained, rounded to sub-angular, grey, trace clay, with some coarse grained gravel		
	28 - 25.72 28 - 28.75 - 27.02 29 - SPT 28.50-28.95 m 8, 16, 22 N=38 - 27.02 29 - SPT 28.50-28.95 m 8, 16, 22 N=38		

This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F01a



COORDS: 329791.2 m E 6243654.9 m N MGA94 56 SURFACE RL: 1.7 m DATUM: AHD

SHEET: 4 OF 10 REV: C DRILL RIG: Hydropower

CONTRACTOR: Hagstrom Drilling Pty Ltd

LOCATION: M5 East Motorway 1524285

JOB NO:

PROJECT: WestConnex - The New M5

INCLINATION: -90° HOLE DEPTH: 87.00 m LOGGED: MBB DATE: 7/1/16 CHECKED: GMcN DATE: 20/1/16

								EE BEI 111. 07.00 III			DATE: 20/1/	_	_
		_	ling	1	Sampling			Field Material Descr	•				_
МЕТНОБ	PENETRATION RESISTANCE	WATER	DEPTH (metres)	<i>DEPTH</i> RL	SAMPLE OR FIELD TEST	GRAPHIC LOG	USCS SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE	CONSISTENCY DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS	LINO	
	н		30 — - - - - 31 —		SPT 30.00-30.17 m 10, 34/20mm N>34		SP	SAND coarse grained, rounded to sub-angular, grey, trace clay, with some coarse grained gravel		VD	Refusal of SPT in second interval		
			32 — - -	<u>31.88</u> -30.15	SPT 31.50-31.95 m 7, 8, 10 N=18	× × × × × × × × × × × × × × × × × × ×	SM	Silty SAND fine to medium grained, rounded to sub-rounded, dark grey-black			Groundwater flowing under pressure		
WB			33 — - - - - 34 —	34.00 -32.27	SPT 33.00-33.45 m 13, 9, 8 N=17	× × × × × × × × × × × × × × × × × × ×				MD		Quaternary	
>	М		- - - 35 — -	-32.21	SPT 34.50-34.95 m 5, 11, 9 N=20		CI	CLAY medium plasticity, dark grey, with some medium grained sand				Quaf	
			- 36 — - -		SPT 36.00-36.45 m 9, 12, 14 N=26					VSt			
	Н		37 — - - - - - -38—	37.00 -35.27	SPT 37.50-37.80 m 30 N=R		SP	SAND fine to medium grained, rounded, pale grey For Continuation Refer to Sheet 5		VD			
			- - - 39 — -										
			40—	-	his report of herebels	unt ha =	004:	n conjunction with accompanying notes and abbreviations.	t h = -	hear	a propored for		

This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F01a



CLIENT: COORDS: 329791.2 m E 6243654.9 m N MGA94 56

DRILL RIG: Hydropower

PROJECT: WestConnex - The New M5

SURFACE RL: 1.7 m DATUM: AHD CONTRACTOR: Hagstrom Drilling Pty Ltd

LOCATION: M5 East Motorway JOB NO: 1524285

INCLINATION: -90° LOGGED: MBB DATE: 7/1/16 HOLE DEPTH: 87.00 m CHECKED: GMcN DATE: 20/1/16

SHEET: 5 OF 10

REV: C

RL3

Drilling Field Material Description **Defect Information** INFERRED AVERAGE DEFECT SPACING WEATHERING GRAPHIC LOG STRENGTH DEFECT DESCRIPTION RQD (SCR) **ROCK / SOIL MATERIAL DESCRIPTION** Is₍₅₀₎ MPa WATER DEPTH (metres) & Additional Observations (mm) GR. LINO DEPTH RL 0 0 0 0 30 31 34 1524285 MASTER.GPJ <<DrawningFile>> 04/03/2016 16:25 8:30.004 Datgel Tools 35 36 37 Continuation of Sheet 4 SANDSTONE fine to medium grained, yellow-brown, rounded, with some clays in bands, very dense EW GAP 8_10.0 LIB FOR NSW.GLB Log GAP CORED BOREHOLE 38.24 m: DS, 8°, Un, Ro, Cn, 50 mm HW 95 (100) 100 38.90 m: B, 9°, Un, Ro, clay Ct SW SANDSTONE medium grained, massive, pale grey, indistinct laminations dip 5-10°, trace lithic fragments 95 100 (100) 39.87 m: B, 10°, Un, Sm, clay Ct 40.00 This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for GAP gINT FN. F02a



CLIENT:

REVISION C REPORT OF BOREHOLE: LDS-BH-1050

COORDS: 329791.2 m E 6243654.9 m N MGA94 56

DRILL RIG: Hydropower

SHEET: 6 OF 10

PROJECT: WestConnex - The New M5 SURFACE RL: 1.7 m DATUM: AHD CONTRACTOR: Hagstrom Drilling Pty Ltd


LOCATION: M5 East Motorway

LOGGED: MBB

INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 87.00 m

DATE: 7/1/16 CHECKED: GMcN DATE: 20/1/16

REV: C



This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for geotechnical purposes only, without attempt to assess possible contamination. Any references to potential contamination are for information only and do not necessarily indicate the presence or absence of soil or groundwater contamination.

GAP gINT FN. F02a



PROJECT: WestConnex - The New M5

CLIENT:

REVISION C REPORT OF BOREHOLE: LDS-BH-1050

COORDS: 329791.2 m E 6243654.9 m N MGA94 56 SURFACE RL: 1.7 m DATUM: AHD


LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 87.00 m SHEET: 7 OF 10 REV: C

DRILL RIG: Hydropower

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MBB DATE: 7/1/16 CHECKED: GMcN DATE: 20/1/16

GAP gINT FN. F02a

RL3





CLIENT: COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

SHEET: 8 OF 10 REV: C

PROJECT: WestConnex - The New M5

DRILL RIG: Hydropower


CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MBB DATE: 7/1/16

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 87.00 m

CHECKED: GMcN DATE: 20/1/16

GAP gINT FN. F02a

RL3





COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SHEET: 9 OF 10 DRILL RIG: Hydropower

SURFACE RL: 1.7 m DATUM: AHD

CONTRACTOR: Hagstrom Drilling Pty Ltd

REV: C


RL3

LOCATION: M5 East Motorway JOB NO: 1524285

PROJECT: WestConnex - The New M5

CLIENT:

INCLINATION: -90° HOLE DEPTH: 87.00 m LOGGED: MBB DATE: 7/1/16 CHECKED: GMcN DATE: 20/1/16





PROJECT: WestConnex - The New M5

REVISION C REPORT OF BOREHOLE: LDS-BH-1050

COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

LOCATION: M5 East Motorway INCLINATION: -90° JOB NO: 1524285 HOLE DEPTH: 87.00 m SHEET: 10 OF 10 REV: C

DRILL RIG: Hydropower

CONTRACTOR: Hagstrom Drilling Pty Ltd LOGGED: MBB DATE: 7/1/16 CHECKED: GMcN DATE: 20/1/16

						_	HOLE DEPTH: 87.00 M					CHECKED: GIVICN		IE:		_	_
			Drilli	ng			Field Material Description	_	_			Defect Information	_			$\overline{}$	_
METHOD	WATER	TCR	RQD (SCR)	DEPTH (metres)	DEPT RL	GRAPHIC LOG	ROCK / SOIL MATERIAL DESCRIPTION	WEATHERING	EL. S.	STR Is ₍₅	ERRED ENGTH	DEFECT DESCRIPTION & Additional Observations	S	DEF SPA (m	RAG EC CIN m)	T G !	LINO
		100	100 (100)	80 - 81 -	-		SANDSTONE WITH 15-20% SILTSTONE LAMINATIONS medium to coarse grained, grey, cross bedded, 0-30° dip	FF	8		*						
23		100	100 (100)	82 - 83 -	- - - - - - - - - -						,	81.71 m: B, 10°, St, Ro, Cn 81.80 m: B, 2°, Un, Ro, carbonaceous material Vr					
HQ3				84 -	- 83.66 -81.93	3	SANDSTONE WITH 5% CARBONACEOUS LAMINATIONS coarse grained, pale grey, 15° dip, planar, with trace siltstone fragments				*						
		100	85	85 -	84.71 82.98 - 85.31 83.58	3	SANDSTONE WITH 10% SILTSTONE LAMINATIONS medium to coarse grained, grey, 10° dip, cross-bedded SANDSTONE WITH 5% SILTSTONE FLECKS				*	84.58 m: B, 12°, PI, Ro, Cn 84.95 m: B, 5°, PI, Ro, Cn					
		100	(100)	86 -	- - - - -		medium grained, massive, grey, sparse laminations dip 5-20°				*	85.97 m: B, 15°, PI, Ro, clay Ct					
	•			 87-	-87.00 -85.2		END OF BOREHOLE @ 87.00 m TARGET DEPTH GROUNDWATER NOT OBSERVED GROUTED TELEVIEWER IMAGING COMPLETED										
				88 -			DOWNHOLE GEOPHYSICS COMPLETED										
				89 -	- - - -												
				90 -			f borehole must be read in conjunction with accom rposes only, without attempt to assess possible co					references to notential contamination are for				FN.	



CLIENT: CDSJV

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 87.00 m SHEET: 1 OF 7 REV: C

DRILL RIG: Hydropower







CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GrGTbI GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ <<DrawingFile>> 04/03/2016 16:25 8:30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 87.00 m SHEET: 2 OF 7 REV: C

DRILL RIG: Hydropower







CLIENT: CDSJV

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 87.00 m SHEET: 3 OF 7 REV: C

DRILL RIG: Hydropower







CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GrGTbI GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ <<DrawingFile>> 04/03/2016 16:25 8:30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 87.00 m SHEET: 4 OF 7 REV: C

DRILL RIG: Hydropower







CLIENT: CDSJV

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 87.00 m SHEET: 5 OF 7 REV: C

DRILL RIG: Hydropower







CLIENT: CDSJV

GAP 8_10.0 LIB FOR NSW.GLB GrGTbI GAP CORE PHOTO 2 PER PAGE 1524285 MASTER.GPJ <<DrawingFile>> 04/03/2016 16:25 8:30.004 Datgel Tools

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway JOB NO: 1524285 COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 87.00 m SHEET: 6 OF 7 REV: C

DRILL RIG: Hydropower







CLIENT: CDSJV

PROJECT: WestConnex - The New M5

LOCATION: M5 East Motorway

JOB NO: 1524285

COORDS: 329791.2 m E 6243654.9 m N MGA94 56

SURFACE RL: 1.7 m DATUM: AHD

INCLINATION: -90° HOLE DEPTH: 87.00 m SHEET: 7 OF 7 REV: C

DRILL RIG: Hydropower



Attachment 2 – Drawing No. MCPN-ARC-CV-DWG-0111, Issue 01, Arcadis



